



Hurricane Preparedness Plan

Small scale projects less than 5,000 square feet in ground area, 2 stories or less

Hurricane Preparedness Plan Address: _____

Construction Project Name: _____

Hurricane Conditions of Readiness:

1. The Texas coast is subject to hurricane storms at various times during the year. The project manager shall comply with the following requirements for hurricane readiness.
2. The contractor's superintendent shall conduct a briefing on the establishment of storm conditions with the project manager. Project manager and superintendent will update work crew on procedures for readiness within 72 hours of a predicted storm.
3. We hereby agree this is for temporary construction-related containers and equipment and does not authorize any permanent use or installation of such containers or equipment.
4. Any construction container or equipment must be placed within the boundaries of the property where construction is occurring, unless otherwise approved in writing by the adjacent property owner.

BELOW IS MY PLAN OF ACTION IN THE EVENT A STORM IS PREDICATED IN THE GULF.

LEVEL 1: (SUSTAINED WINDS GREATER THAN 60 MPH EXPECTED WITHIN 72 HOURS)

1. Normal daily job site cleanup and good housekeeping practices. Collect and store in piles or containers all scrap lumber, waste material, and rubbish for removal and disposal at the close of each workday.
2. Maintain the construction site at the close of each day.
3. Maintain the construction site including storage area, free of accumulation of debris.
4. Stack form lumber in neat piles less than four (4) feet high. Remove all debris, trash or objects that could become missile hazards.
5. Contact project manager for condition of readiness and completion of required action.

LEVEL 2: (SUSTAINED WINDS GREATER THAN 60 MPH EXPECTED WITHIN 48 HOURS)

1. Maintain "LEVEL 1" requirements and commence securing operations as necessary for "LEVEL 4" which cannot be completed within 18 hours.
2. Cease all routine activities that might interfere with securing operations.
3. Commence securing and stow all gear and portable equipment.

